

Thrissur Corporation Electricity Department (TCED)

Appointment of Contractor for New 110/11kV Substation works -Tender Queries

Tender No. TCED / RDSS : 2405/22

| Sr. No | RFP Reference | Query | TCED- Reply |
|--------|--|---|--|
| 1 | BOQ3; Sl.No.1.1 | Supply of 110kV, 1c x 630 sq.mm Aluminium corrugated Sheated Aluminium Cable as per standard technical specification. Please confirm, how many cables or runs to be laid. | 2R x 3 x 1C x 630sq.mm (Each cable per run is 750 Meter), total cable length is 4500 Meter - cables shall be supplied and laid. |
| 2 | Not Applicable | Kindly inform which is the brand of SCADA being used by TCED, shall we include the cost of integrating the same | No. SCADA compatible equipment's only to be supplied. |
| 3 | Not Applicable | The stages of payment for civil item for substation is mentioned both in supply as well as labour and it is a LS item. | Refer BOQ1-41; BOQ2-3; Bidder shall be calculated both Civil item and Labour parts as per Substation Constructions activities and payments as per SBD. |
| 4 | Not Applicable | Soil test report of substation room and yard area to be given to design foundation and for quoting purpose as item is LS. | Refer BOQ-2, Sl.No.: 1.1 &2 |
| 5 | BOQ4 | 110kV Cable laying excavation quantity is mentioned as 1 and unit is Nos. Kindly provide us the envisaged quantity and correct the unit of measurement. | 2R x 3 x 1C x 630sq.mm (Each cable per run is 750 Meter), total cable length is 4500 Meter - cables shall be supplied and laid and Excavations to be done accordingly. |
| 6 | Not Applicable | 200mm HDPE pipe used for horizontal duct drilling purpose is welded to form the required length. Hence no coupling collar etc is envisaged. Kindly accept the same. | Refer BOQ-4, Sl.No.: 8. |
| 7 | Not Applicable | The item, quantity and unit in sections supply and labour for 110kV Under ground cable is to be corrected. | As per BOQ-4, it's to be considered as LS or 1 No. |
| 8 | 2. Qualification Requirements (2.1- Technical) | Similar work: We have technical qualification as mentioned in clause 2.1.3 (a). Also we would like to bring to your attention that electrical generation for small thermal plant is at a system voltage of 11kV. Hence, we request you to consider the same as per CI 2.1.3(a). | Refer SBD, Page-18, Part-1, Sl.No.2.1.3 (a) & (b). |
| 9 | Financial | Networth: We are a partnership firm and as per the principle of calculation networth of partnership firm calculation is as per enclosure. Kindly confirm this is acceptable for partnership firm. The networth will vary according to the drawing out of cash by the partners in each year | As per RFP; Any relaxations in the PQ condition will be published as corrigendum. |